BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: EE/RRND/Tend/02/2020-21 Date: 10.06.2020

Indet No: BBMP/2020-21/RD/WORK_INDENT42933

SCHEDULE -B

Name of Work: Construction of drain at selected reaches in ward no 16 Jalahalli

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	253.80	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per	Cum	372.00	Rupees Three Hundred Seven Two Only
2	35.25	KSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in oundation, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	5667.00	Rupees Five Thousand Six Hundred Sixty Seven Only
3	74.02	Providing and laying lain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications.-do- Wall & bottom thickness 15cm	Cum	7409.00	Rupees Seve Thousand Fo. Hundred Nine Only
4	5.18	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specification No. KBS 4.6.3 - do - TMT bars Fe 500	Tonne	78827.00	Rupees Seventy Eight Thousand Eight Hundred Twenty Seven Only
5	235.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.- do - 7.5 cms thick	Cum	778.00	Rupees Seven Hundred Seven Eight Only
6	1472.00	Providing champering edges to stone slab 2.5 cms wide as per specifications (Only champering length shall be recorded)	Mtrs	64.00	Rupees Sixty Four Only
7	235.00	Providing one line dressing to granite stone slab /granite sone masonry as per specifications.	Sqm	996.00	Rupees Nine Hundred Ninety Six Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner